



April 7, 2026

BIDDERS:

RE: Township of Havelock- Belmont- Methuen
Contract No. 2026-01
Reconstruction of County Road 48 (George Street)
Addendum No. 1

Please find outlined below a detailed summation which forms Addendum No. 1, of which shall be included and become part of the Contract Tender Documents.

1- **(Form of Tender – Part 6) – Itemized Bid Sheets – Pages 79-126**

Question and Clarifications

Phase 1 – Part 1A

Q1 – Item A27/A28 (PH1) – Curb and Gutter (600.060). Could these quantities be reviewed as we are only seeing a total of 480m of 600.060 curb in PH1?

A1 – Please see revised bid sheets.

Q2 - Item B3 (PH1) – Connection of New STM to Ex. STM. Can this quantity be reviewed? We are seeing 6 connections total.

A2 – Please see revised bid sheets.

Q3 - Item B4 (PH1) – 2400mm STM MH. Can this quantity be reviewed? We are seeing 1 total (ST11).

A3 – Please see revised bid sheets.

Q4 - Item B8 (PH1) – Double CB. Can this quantity be reviewed? We are seeing 1 total (DCB17).

A4 – Please see revised bid sheets.



Q5 - Item B11 (PH1) – 1500mm Conc STM. Can this quantity be reviewed? We are seeing 180m total in PH1.

A5 – Please see revised bid sheets.

Q6 - Item B12 (PH1) – 1220mm x 1920mm Elliptical STM. Can this quantity be reviewed? We are seeing 75m total in PH1.

A6 – Please see revised bid sheets.

Q7 - Item C5 (PH1) – 1200mm SAN MH. Can this quantity be reviewed? We are seeing 2 total (SA21, SA20)

A7 – Please see revised bid sheets.

Phase 2 – Part 2A

Q8 - Item A27/A28 (PH2a) – Curb and Gutter (600.060). Could these quantities be reviewed as we are only seeing a total of 210m of 600.060 curb in PH1?

A8 – Please see revised bid sheets.

Q9 - Item B26 (PH2a) – 2400mm STM MH. Can this quantity be reviewed? We are seeing 2 total (ST10, ST10a).

A9 – Please see revised bid sheets.

Q10 - Item B27 (PH2a) – Single CB. Can this quantity be reviewed? We are seeing 1 total (CB33).

A10 – Please see revised bid sheets.

Q11 -Item C18 (PH2a) – 200mm PVC SAN. Can this quantity be reviewed? We are seeing 112m total.

A11 – Please see revised bid sheets.



Phase 2 – Part 2B

Q12 -Item A17 (PH2b) – Removal and Reinstatement of Fence. Can you clarify what property is intended for the 50m of removal and reinstatement of fencing?

A12 – Removal and Reinstatement of fencing can be found in front of Civic 63; as well as in front of the existing sidewalk being removed beside Civic 72.

Q13 - Item A27/A28 (PH2b) – Curb and Gutter (600.060). Could these quantities be reviewed as we are only seeing a total of 85m of 600.060 curb in PH1?

A13 – Please see revised bid sheets.

Phase 2 – Part 2C

Q14 - Item B14 (PH2c) – 900mm HDPE STM. Can you confirm that this item is meant to be specified as concrete pipe (as shown on drawings) rather than HDPE stated in tender form?

A14 – The 900mm storm pipe in question is to be 100-D RCP as stated on the drawings. Please see revised bid sheets.

Q15 - Item C5 (PH2c) - 1200mm SAN MH. Can this quantity be reviewed? We are seeing 3 total (SA27, SA28, SA29)

A15 – Please see revised bid sheets.

Phase 3 – Part 3A

Q16 -Item B5 (PH3a) – 1200mm STM MH. Can this quantity be reviewed? We are seeing 1 total (ST14).

A16 – Please see revised bid sheets.

Q17 - Item B7 (PH3a) – 1800mm STM MH. Can this quantity be reviewed? We are seeing not seeing any 1800mm STM MHs in this phase.

A17 – Please see revised bid sheets.

Q18 - Item B10 (PH3a) – 150mm PVC Storm Sewer. Can this quantity be reviewed? We are seeing 12 storm services totaling 100m.

A18 – Please see revised bid sheets.



Q19 - Could an item be added for the 300mm PVC CB laterals (8m) alike other phases?

A19 – Please see revised bid sheets.

Q20 - Could an item be added for the 750mm RCP (ST13A to ST14 – 14.6m)

A20 – Please see revised bid sheets.

Q21 -Item C5 (PH3a) - 1200mm SAN MH. Can this quantity be reviewed? We are seeing 3 total (SA23, SA24, SA25)

A21 – Please see revised bid sheets.

Phase 3 – Part 3B

Q22 -Item B3 (PH3b) – Connection of New STM to Ex. STM Sewer. Can this quantity be reviewed? We are seeing 3 total.

A22 – Please see revised bid sheets.

Q23 - Item B4 (PH3b) – 1500mm STM MH. Can this quantity be reviewed? We are not seeing any 1500mm STM MHs in this phase.

A23 – Please see revised bid sheets.

Q24 - Item B5 (PH3b) – 150mm PVC STM. Can this quantity be reviewed? We are not seeing any storm services in this phase.

A24 – Storm service laterals to be installed fronting the existing Remax Building, and Civic # 12. Revised drawings will be issued to the successful bidder.

General Inquiries

Q25 - Items A24/25 (all phases) – HL3 and HL8 HMA. Could it be explained that the HL3 item has a much higher quantity than the HL8 item being that per cross sections on CS-01 it appears that all asphalt areas receive 50mm HL3/50mm HL8.

A25 – Please see revised bid sheets.

Q26 - Do storm services require cleanouts?

A26 – No, storm service cleanouts are not required.



Q27 -Could you provide some additional insight with the “Sump Pump/Subdrain Pipe Connections” item? Are we to assume this is in the scenario in which the property does not receive a storm service and the contractor is to connect to existing sump pipe line to the new subdrain?

A27 – Every property is to receive a storm service to the property line limits. A connection is than to be made from the new storm service to the existing storm service (sump pump/subdrain pipe) when encountered.

Signed acknowledgement of such addenda must be included to form a complete and final bid submission.

Contractor

Signature of Authorized Signing Officer

Date